

SISTEMA SANCAD - PLANILHA DE DADOS FINAIS
SERVIÇO INTERMUNICIPAL DE ÁGUA E ESGOTO
SIMAE - CAPINZAL E OURO
REDE ESGOTO KENNEDY FUNDO DE LOTE

05/06/2020

Trecho	PVM	PVJ	Comp (m)	CTM (m)	CTJ (m)	CCM (m)	CCJ (m)	PRFM (m)	PRFJ (m)	Diam (mm)	Decl (m/m)	Q Real Ini (l/s)	Q Real Fim (l/s)	Veloc Ini (m/s)	Veloc Fim (m/s)	Veloc Crit (m/s)	Trativa (Pa)	H/D Ini	H/D Fim	Observ.
006-001	PV029	PV025	51.00	501.000	492.000	500.150	491.150	0.850	0.850	150	0.17647	0.037	0.068	1.81	1.81	1.77	15.74	0.09	0.09	TQ 0.052
005-001	PV022	PV023	52.00	510.000	502.000	509.150	501.150	0.850	0.850	150	0.15385	0.038	0.070	1.72	1.72	1.80	14.15	0.10	0.10	
005-002	PV023	PV024	42.00	502.000	500.000	501.150	499.150	0.850	0.850	150	0.04762	0.069	0.126	1.14	1.14	2.06	5.71	0.13	0.13	TQ 0.052
005-003	PV024	PV025	71.00	500.000	492.000	499.098	491.098	0.902	0.902	150	0.11268	0.121	0.221	1.54	1.54	1.87	11.12	0.10	0.10	
005-004	PV025	PV026	80.00	492.000	486.000	491.098	485.150	0.902	0.850	150	0.07435	0.216	0.397	1.34	1.34	1.96	8.06	0.11	0.11	
005-005	PV026	PV027	65.00	486.000	483.000	485.150	482.150	0.850	0.850	150	0.04615	0.264	0.484	1.13	1.13	2.06	5.57	0.13	0.13	TQ 0.050
005-006	PV027	PV028	84.00	483.000	478.000	482.100	477.100	0.900	0.900	150	0.05952	0.325	0.596	1.24	1.24	2.01	6.78	0.12	0.12	
005-007	PV028	PV004	57.00	478.000	477.000	477.100	476.150	0.900	0.850	150	0.01667	0.367	0.673	0.79	0.79	2.31	2.53	0.16	0.16	TQ 0.067
004-001	PV017	PV018	48.00	506.000	498.000	505.150	497.150	0.850	0.850	150	0.16667	0.035	0.064	1.77	1.77	1.79	15.06	0.09	0.09	
004-002	PV018	PV019	44.00	498.000	494.000	497.150	493.150	0.850	0.850	150	0.09091	0.067	0.123	1.43	1.43	1.91	9.42	0.11	0.11	
004-003	PV019	PV020	43.00	494.000	490.000	493.150	489.150	0.850	0.850	150	0.09302	0.099	0.181	1.44	1.44	1.91	9.59	0.11	0.11	TQ 0.050
004-004	PV020	PV021	27.00	490.000	486.000	489.100	485.100	0.900	0.900	150	0.14815	0.118	0.217	1.70	1.70	1.81	13.75	0.10	0.10	
004-005	PV021		54.00	486.000	486.000	485.100	484.830	0.900	1.170	150	0.00500	0.158	0.290	0.52	0.52	2.64	1.00	0.22	0.22	FIM
003-001	PV016	PV014	22.00	516.000	515.000	515.150	514.150	0.850	0.850	150	0.04545	0.016	0.030	1.12	1.12	2.07	5.50	0.13	0.13	TQ 0.050
002-001	PV012	PV013	36.00	520.000	516.000	519.150	515.150	0.850	0.850	150	0.11111	0.026	0.048	1.54	1.54	1.87	11.00	0.10	0.10	
002-002	PV013	PV014	21.00	516.000	515.000	515.150	514.150	0.850	0.850	150	0.04762	0.042	0.076	1.14	1.14	2.06	5.71	0.13	0.13	TQ 0.050
002-003	PV014	PV015	13.00	515.000	514.000	514.100	513.100	0.900	0.900	150	0.07692	0.067	0.123	1.35	1.35	1.95	8.28	0.11	0.11	TQ 0.108
002-004	PV015		67.00	514.000	498.000	512.992	497.042	1.008	0.958	150	0.23806	0.116	0.213	2.01	2.01	1.72	19.84	0.09	0.09	FIM
001-001	PV001	PV002	46.00	492.000	488.000	491.150	487.150	0.850	0.850	150	0.08696	0.034	0.062	1.41	1.41	1.92	9.10	0.11	0.11	
001-002	PV002	PV003	41.00	488.000	485.000	487.150	484.150	0.850	0.850	150	0.07317	0.064	0.117	1.33	1.33	1.96	7.96	0.12	0.12	TQ 0.067
001-003	PV003	PV004	48.00	485.000	477.000	484.083	476.083	0.917	0.917	150	0.16667	0.099	0.181	1.77	1.77	1.79	15.06	0.09	0.09	
001-004	PV004	PV005	40.00	477.000	473.000	476.083	472.150	0.917	0.850	150	0.09833	0.494	0.907	1.47	1.47	1.90	10.01	0.11	0.11	
001-005	PV005	PV006	53.00	473.000	473.000	472.150	471.885	0.850	1.115	150	0.00500	0.533	0.978	0.52	0.52	2.64	1.00	0.22	0.22	TQ 0.050
001-006	PV006	PV007	37.00	473.000	472.000	471.835	471.100	1.165	0.900	150	0.01986	0.560	1.028	0.84	0.84	2.27	2.89	0.16	0.16	

Trecho	PVM	PVJ	Comp (m)	CTM (m)	CTJ (m)	CCM (m)	CCJ (m)	PRFM (m)	PRFJ (m)	Diam (mm)	Decl (m/m)	Q Real Ini (l/s)	Q Real Fim (l/s)	Veloc Ini (m/s)	Veloc Fim (m/s)	Veloc Crit (m/s)	Trativa (Pa)	H/D Ini	H/D Fim	Observ.
001-007	PV007	PV008	42.00	472.000	472.000	471.100	470.890	0.900	1.110	150	0.00500	0.591	1.084	0.52	0.52	2.64	1.00	0.22	0.22	TQ 0.050
001-008	PV008	PV009	53.00	472.000	469.000	470.840	468.100	1.160	0.900	150	0.05170	0.629	1.155	1.18	1.18	2.04	6.08	0.13	0.13	TQ 0.050
001-009	PV009	PV010	35.00	469.000	466.000	468.050	465.100	0.950	0.900	150	0.08429	0.655	1.202	1.40	1.40	1.93	8.88	0.11	0.11	TQ 0.056
001-010	PV010	PV011	24.00	466.000	462.000	465.044	461.094	0.956	0.906	150	0.16458	0.672	1.234	1.76	1.76	1.79	14.91	0.09	0.09	
001-011	PV011	FIM	44.00	462.000	458.000	461.094	457.150	0.906	0.850	150	0.08964	0.705	1.293	1.43	1.43	1.92	9.32	0.11	0.11	FIM